

FREE - New Equipment Checkout



Vulcan & Wolf New Equipment Checkout - A Partnership with Hobart Service

To ensure new Vulcan and Wolf equipment has been properly installed and is operating correctly, a certified Hobart Service technician will:

- Verify that the proper gas type (L.P. or natural) has been connected to the equipment
- Verify that the proper voltage and electrical connections have been made
- Verify that proper pressure regulators have been installed and adjusted, when applicable
- Verify that gas supply size and pressure is adequate
- Verify that proper water, steam, drain supplies and connections have been made
- Check to ensure the ventilation system is operating correctly
- Check pilot and burner adjustments
- Verify thermostat operation, including calibration, when required
- Check functional parts of operation, for example: doors, lids, valves, etc.
- Advise on preventive maintenance procedures

To schedule your free checkout, visit www.hobartservice.com/officelocator to find your local Hobart Service office. Please keep in mind:

- Equipment must be completely installed and ready to operate before the equipment checkout request is made.
- Equipment checkout should be completed within 90 days after installation.